

The Construction of PMS (People Mover System) Viaduct within the boundaries of Qatar Foundation - Education City comprises construction of 1060m long void formed post tensioned reinforced deck viaduct of 8m width with an average height of 5.7m over existing ground level. Two elevated stations namely QNCC (Qatar National Convention Centre) and Sidra will be constructed with architectural finishes, landscaping and MEP works. The duration of the project is 240 calendars days with a maintenance period of 1 year.

Client Qatar Petroleum

Location Doha / Qatar

Contract Date 15 September 2013

Completion Date In Progress

{backbutton}